

Notes:

1- Trees shall be of quality prescribed in crown observations and root observations details and specifications.

2- See specifications for further requirements related to this detail.

Trunk caliper shall meet ANSI Z80 current edition for root ball size.

Root ball modified as required.

Round-topped soil berm 4" high x 8" wide above root ball surface shall be centered on the downhill side of the root ball for 240°. Berm shall begin at root ball periphery.

Modified soil. Depth varies. (See soil preparation plan).

Central leader. (See crown observations detail).

Original slope should pass through the point where the trunk base meets substrate/soil.

Prior to mulching, lightly tamp soil around the root ball in 6" lifts to brace tree. Do not over compact. When the planting hole has been backfilled, pour water around the root ball to settle the soil.

4" layer of mulch. No more than 1" of mulch on top of root ball. (See specifications for mulch).

Original grade.

Bottom of root ball rests on existing or recompacted soil.

SECTION VIEW

URBAN TREE FOUNDATION © 2014
OPEN SOURCE FREE TO USE



TREE ON SLOPE 5% (20:1) TO 50% (2:1) (EXISTING SOIL MODIFIED)